Sl. No.	Name of the articles	Quantity
43	Deal wood racks	2
44	Tin lymph boxes	2
45	Iron clamps	2
46	Kipps's apparatus, broken	1
47	Rattan basket for bottle	1
48	Chamber pot with lid, iron	1
49	Iron rods	2
50	Leather belts with buckle	3
51	Wire gauge door	1
52	Razor	1
53	Syringe Glass 1 c. c.	1
54	Rubber tubing, old	3 yards.
55	Locks	6
56	Iron creso drum	1

A. S. VENKATACHALAM,
Superintendent.

OFFICE OF THE ASSISTANT ENGINEER, HEADQUARTER RANGE, MYSORE.

Notification dated 19th November 1936.

1. Sealed tenders will be received at the Office of the Assistant Engineer, Headquarter Range, Mysore, up to 12 Noon on 30th November 1936, for constructing (i) Out-house shed to the rear of block A; (ii) extending to the east *i.e.*, block C; (iii) extending to the west *i.e.*, block B. Tenders for each of these will be considered separately and works, will at the discretion of the Superintending Engineer, be entrusted to different, or one contractor, in the interest of speedy completion of the work.

2. Tenders in the prescribed form obtainable from the Office of the Assistant Engineer, Headquarter Range, Mysore, on payment of Rupee one for each form should be addressed to the Assistant Engineer, Headquarter Range, and should be superscribed as "Tender for constructing 'Out-house shed', 'Block B' or 'Block C' to the new Railway Office Building at Mysore now under construction." The name of the tenderer should also be superscribed on the sealed cover.

3. Each tender must be accompanied by a deposit of Rs. 5,000 (Rupees five thousand only) in cash or Government Promissory Notes or Mysore Government Bonds at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. (Cash amount will not carry any interest).

4. The tenders will be opened in the presence of such tenderers who wish to be present on 30th November 1936, at 3 P.M. The final acceptance of the tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reasons whatever, for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Assistant Engineer's Office, in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute the Agreement in the departmental schedule contract form for the due fulfilment of the contract.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. Copies of contract documents, estimates and drawings, may be seen at any time at the Office of the Assistant Engineer, Headquarter Range, Mysore, on all working days between 11 A.M. and 5 P.M.

8. Specific rate should be given for each item in the schedule and the rate should be in rupees, annas and in multiples of three pies and expressed in words and figures.

9. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates tendered should include all such lumpsum items.

10. No alterations which are made by the tenderers in the contract documents in the nomenclature of the sanctioned sub-heads will be recognised and if corrections are made, the tenders will be liable to rejection.

11. There should be no corrections or erasers in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the Tenderer.

12. No reference should be made to the Public Works Department current schedule of rates.

13. On the event of the tender being submitted by a Firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power of attorney, authorising him to do so.

14. When once the rates tendered have been accepted they will not be revised under any circumstances. In regard to items of work not tendered, the rates to be proposed by the Assistant Engineer, Headquarter Range, Mysore, and approved by the Superintending Engineer, shall be final and legally binding on the tenderer.

15. The quantities as estimated are only approximate and are liable to alterations, omissions, deductions, or additions, at the discretion of the Assistant Engineer, or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those estimated for.

16. The work should be completed as per departmental specifications for different items and handed over to the Public Works Department by the 1st week of June 1937, failing which the Assistant Engineer may, at his discretion, levy a penalty of Rs. 50 per day, which will be recovered from the Contractor's outstandings for the period exceeded by him till the work is completed and handed over.

17. In all matters of dispute of any kind, not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer, shall be final and legally binding.

18. The earnest money of rejected tenders will be returned on surrender of the receipts originally granted, along with an application, to the Assistant Engineer, Headquarter Range, Mysore.

19. No claims for damages for delays caused by Officers of the Department in the execution of the work will be considered, whatever may be the reason for such delays. Contractors should bear this in mind when tendering for work. Extension of time due to delays caused by the departmental officers will however be considered on the merits of each case.

20. The Contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Assistant Engineer, in the interest of the work shall be accepted by the tenderer at the rates fixed by the Assistant Engineer, and the tenderer will pay the hire, etc., on Machinery at the prescribed per cent per annum of the booked value of the tools and plant supplied from the date of taking over of tools and plant from the stores to the date of return to the Stores, the dates considered being, the dates of acknowledgments of the vouchers in each transaction.

22. The Contractors should arrange for the payment of Royalty and Tolls.

Note (*A*).—The Contractors should at their own cost—

(1) Provide rods, stakes, ropes and labours required in setting out the works.

(2) Provide all necessary scaffolding, centering labour and appliance for hoisting.

(3) Provide power mortar mill and shed to keep materials under cover and also for workmen.

(4) Arrange for protecting work during inclement weather.

(5) Supply requisite temporary lights, water-cisterns, water-shoots, coverings to masonry tile pieces to steps, sieves, parahs, or measures shoring and other requisite protection during the progress of the work.

(6) Supply all water required for work and workmen and shall provide latrines, drainages, etc.

(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.

(8) Provide arrangements for pumping and bailing from excavations and foundations, wherever and whenever necessary with their own pumping apparatus, including necessary leading drains, sump pits, etc.

(9) Wash floors at completion and leave the whole of the work and premises in a clean and orderly condition, etc.

(10) Afford facilities to any other parties employed upon the work, so that their work may proceed during the progress of the contract and give such persons the use of ordinary scaffolding and ladders.

Note (B).—It is the business of the Contractors to make their own arrangements for the quarries and supplies of materials.

23. The rates for wood work for all works quoted should be based on the rates of the departmental supply as noted below. Only Mysore Teak selected from the Mysore Government Depots must be used.

24. Work to the extent of Rs. 5,000 each on out-house shed and block 'B' and Rs. 10,000 for block 'C' will have to be carried out each month.

Prevailing Government rates at Mysore Forest Depot for Mysore teak is as follows:—

	Rs.	a.	p.	
(1) Selected 1st class logs ..	.. 2	8	0	per c.ft.
(2) Cut scantling of sizes 3″×4″ ..	.. 3	4	0	,,
(2)(*a*) Do 3″×5″ to 4″×7″	.. 3	12	0	,,
(3) Planks 1″ to 1¾″ to required sizes..	.. 4	8	0	,,

Rate list for Out House, Block B, or Block C (the particular work tendered for should be retained, striking off the others).

Sl. No.	Items of work	Unit	Rate for Ground Floor		Rate for 1st Floor		Rate for 2nd Floor	
			In figures	In words	In figures	In words	In figures	In words
			Rs. a. p.		Rs. a. p.		Rs. a. p.	
1	Earthwork excavating foundations and filling in basement with watering and consolidating	C.yd.						
2	*Broken granite stone jelly concrete in lime mortar with tamping in layers of not more than 4" for foundation	C.ft.						
2a	* Do in surki mortar	"						
	Note.—Screened and slaked lime of approved quality only to be used in the proportion of 1 of slaked lime to 2 of good river sand for mortar and 1 of slaked lime : 1½ river sand : ½ surki for surki mortar ..							
3	Size stone in lime mortar with bond stones 6 feet apart for foundation and basement	C.ft.						
4	Face dressing 2 lines for exposed masonry	Sq.ft.						
5	Burnt stone slabs 6" thick one lime dressed on all the faces for plinth and steps including supplying and fixing in mortar	"						
5a	Three line dressing for slabs	"						
6	Providing and fixing burnt stone slabs 6" thick one line dressed for lintels of doors, cill and lintels of windows and stone plates below R.C. slabs of roofs	"						
7	Burnt brick in composite mortar mixed with ⅛ cement for superstructure	C.ft.						
7a	Burnt brick in lime mortar	"						
8	Wire cut brick in cement mortar with bond slabs at 4½ feet intervals for pillars with caps and bases, plastered with light coloured cement to shape as per design (Ground and first floor)	"						
9	Plastering with chunam mortar for walls, including rounding of all projecting and receding corners with cement mortar 1:4 for a width of 3" both sides	Sqr.						
10	Pointing the stone mosonry with snowcrete 1:3 of sand and lining nicely for basement	"						
11	Hall's Sanitary Distemper colour washing of different required colours, two coats	"						

12	Tested Rolled steel girders as per British standard specification, including lifting and hoisting and boxing with cement, mortar and terrace brick reinforced with galvanized steel-tex net tied alround, with one coat of Anticorrosive paint and fixing with cement concrete in walls	Cwt.
13	Flooring with cement concrete 1 : 2 : 4—1½″ thick on 6″ lime concrete with topping of red cement ¼″ thick finished with ironite 2½ lbs. per square and cut to the required tile pattern where required with all corners rounded	Sqr.
14	Pressed coloured cement red tile flooring to the W.C.'s. over 6″ lime concrete and pointing with cement ..	,,
14*a*	Glazed tile (British make) flooring	Sqrs.
14*b*	Glazed tile dadoo with angles and borders	,,
15	Partition wall with H.B. hoop iron or other wall reinforcement in every third course 4½″ thick in cement mortar including plastering with lime mortar 1 : 3 ..	Sq.ft.
16	Teakwood newel staircase 12″ tread 6″ rise on cut stringers with platforms width of steps 4½ to 5 feet including ceiling with ¾″ thick plank complete with delux varnish 2 coats for ceiling, etc.	Sq.ft.
16*a*	Reinforced cement concrete cantilever stair case 4½ to 5 feet wide including teakwood facing with brass kick plate bottom plastering, etc., complete	Sq.ft.
17	Teakwood hand railing with turned balusters with top and bottom rails 3″ ×5″ including delux varnish for bal balusters and duco finish for hand rail	R.ft.
17*a*	Teakwood railing with flat steel uprights and runners and teak moulding at top and cement concrete base wall	,,
18	Roofing with brick and cement concrete (granite jelly) terrace with ½″ bars 6″ centres for spans above 10 ft. with 3″ cement concrete slab and finished with extra floor of 1½ inch cement concrete and ½″ plaster with water proof coloured cement cut to tile pattern and with ceiling plaster	Sqrs.
18*a*	Do do do with ⅜″ bars 4½″ C. to C. for spans less than 10 ft. with 2″ cement concrete slab and finished as in 18	,,

Sl. No.	Items of work	Unit	Rate for Ground Floor		Rate for 1st Floor		Rate for 2nd Floor	
			In figures	In words	In figures	In words	In figures	In words
			Rs. a. p.		Rs. a. p.		Rs. a. p.	
18*b*	Reinforced brick concrete terrace for spans above 10 ft. with $\frac{1}{2}$" bars and 3" cement concrete slab with 4" kappi on top and two courses of flat tiles and plastered smooth top and bottom	Sqrs.						
18*c*	Do do do with $\frac{3}{8}$" bars for spans below 10 ft. with 2" slab do do ..	,,						
19	Coving for ceiling as per design to be furnished including rounding at corners with cement mortars	R.ft.						
20	Providing and fixing cast-iron railing with teak top rail as per design to be furnished including painting with aluminium or duco paint	,,						
21	Cement perforated ventilators as per design to be furnished $1\frac{1}{2}$" thick with 3" wide band all round and 1 per cent reinforcement, neatly finished	Sq.ft.						
22	Skirting with 9" high $\frac{3}{4}$" thick, cement plaster finished with $\frac{1}{4}$" coloured cement for interior walls as per design	R.ft.						
23	Teak wood doors with frames 3"×5" without bottom cills and having $\frac{1}{3}$ pannelled $\frac{2}{3}$ glazed (Translucent $\frac{1}{8}$" thick) with $1\frac{3}{4}$" thick shutters including "acme" brass fittings, rim door locks with handles, three finger plates 12" by 4" as per design with 6" brass hinges and two 6" hooks, brass screws barrel bolts of suitable sizes, etc., including delux water proof varnish or paint 2 coats with semi-circular or rectangular glazed ventilators, if any, as per design	Sq.ft.						
23*a*	Do do with $\frac{2}{3}$ pannelled and $\frac{1}{3}$ glazed shutters ..	,,						
24	Teakwood windows 3"×5" frame work with $1\frac{1}{2}$" glaze shutter opening outside in four halves with rectangular or semi-circular ventilators at top including iron bars $\frac{3}{4}$" diameter at 4" apart, brass hinges, brass hooks, 2" rings, casement adjusting stap, etc., complete, including 2 coats of delux varnish or paint	Sq.ft.						
24*a*	Do without bars	,,						
24*b*	Do with bars and pannelled shutters ..	,,						
25	Paving stone slabs cut to square and 2 line dressed including pointing with cement, concrete bed, etc., complete	Sq.ft.						

	Extra for Out-house Shed.	
26	Steel truss for 30 ft. span 10 ft. C. to C. as per design to be furnished including cast iron fixing shoes, bolts, nuts, etc., complete with hoisting and fixing, painting, etc.	Cwts.
27	Roofing with Trafford red sheets on 2″ × 2″ × ¼″ ∠ purlins at required intervals including fixing with hooks, bolts, washers, etc.	Sqrs.
	Other items.	
28	Cement concrete with granite jelly 1 : 2 : 4	C.ft.
29	Reinforced cement concrete 1 : 2 : 4 for lintels	,,
30	Delux painting 2 coats with required tent	..
31	Delux varnishing do	..
	For 2nd Floor only.	
	Hollow roofing with reinforced cement concrete joists and brick nogging on top flange and reinforced cement concrete joists and slabs for ceiling on bottom flange, including bottom plastering, kappi in lime and two courses of flat tiles with plastering on top (Reinforcements as per design). For cement concrete only granite jelly to be used in proportion of 1 of cement, 2 of sand, and 4 of jelly	..

Note.—(1) Rates quoted should be for good quality of materials and workmanship to satisfy the standard departmental specifications.
(2) In the case of out house only rates for ground floor need be given.
(3) Only granite jelly should be used for all cement concrete works.

S. RAMASWAMY,
Assistant Engineer.